

15-095-30027-0000

R.

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

STATE RECEIVED
9-26-79
SEP 26 1979
CONSERVATION DIVISION
Wichita, Kansas
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

Operator's Full Name Rains & Williamson Oil Co., Inc.

Complete Address 220 W. Douglas, 435 Page Court, Wichita, Ks. 67202

Lease Name Russell "A" Well No. 1

Location C SE SW Sec. 36 Twp. 30s Rge. 7 (E) (W) X

County Kingman Total Depth 4714

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase Ks. 67524 License No. 683

Operation Completed: Hour 12 N Day 21 Month 9 Year 1979

The above well was plugged as follows:

209' 8 5/8" casing w/175 sax cement. 5 1/2" casing set at 4709' w/150
sax cement. Preforated at 4448'-Push plug to 4400'-Sand back to 4350'-
Top sand w/ 5 sax mixed cement w/ dump bailer. Pull 3715' 5 1/2" casing.
Allied mixed & pumped 4 sax hulls & 25 sax 50/50 posmix cement ahead
of 4 sax hulls-25 sax gel-150 sax 50/50 posmix cement w/ 4% gel & 3%
cc to top of casing. Shut in w/400# pressure.

INVOICED
DATE 9-26-79
INV. NO. 0545-W

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor