

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-085-21,121-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Coastal Oil & Gas

Complete Address Box 889 Great Bend, Kansas 67530

Lease Name Durant Well-No. 4

Location 660' FEL & 980' FNL C /SE NE/4 Sec. 36 Twp 30 Rge. 7W (East)(West)

County Kingman Total Depth 4900'

Abandoned Oil Well Gas Well XX Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. 683

Operation Completed: Hour: 11⁵⁰ AM Day: 28 Month: 12 Year: 19 81

Plugging Operations attended by Agent?: All Part X None

The above well was plugged as follows:

335' of 8 5/8" SP 5 1/2' set @ 4898' W/250 sks

Perfs @ 3878' to 3882' Set Cast Iron plug @ 3800'

Top perf @ 3030' to 3050' Push plug to 3060'

Sand back to 3000' & W/5 sks

Pump 15 gel, 6 hulls, 10 gel and displace W/150 sks common cement

2% gel 3% C.C. Cemented by Howco Rec. 2440' of 5 1/2' csg.

SFP-360#

RECEIVED
STATE CORPORATION COMMISSION
1-5-82
54082

I hereby certify that the above plugging instructions were given as herein stated.

INVOICED

Signed: M. B. Sullivan
Conservation Division Agent

DATE 1-20-82

INV. NO. 89-027W