

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 14 1974  
6-14-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Oil Property Management Inc

Complete Address 300 Insurance Bldg Wichita, KS

Lease Name Leckner Well No. 2

Location C NE/NW Sec. 36 Twp. 30<sup>S</sup> Rge. 7 (E) (W)

County Kingman Total Depth 4707

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Russ Casing Pulling Co Inc

Address Box 1082 Great Bend, KS License No. 623

Operation Completed: Hour 11:00 AM Day 13 Month 6 Year 1974

The above well was plugged as follows:

230 ft 8 5/8 surface cemented with 180 sacks. 4704 ft 5 1/2 long string  
cemented with 125 sacks. Open hole. Sand to 4650 ft, 5 sacks cement  
with bailer. Pulled 4000 ft 5 1/2. Set 20 ft rock bridge at 380 ft.  
Fill hole with 7 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 6/14/74

INV. NO. 9305-W

Operator: McClure Oil Company  
#2 Lechner  
C NE NW Sec. 36-30S-7W  
Kingman County, Kansas

Contractor: Rains & Williamson Oil Co.  
Commenced: 11/13/65  
Completed: 11/25/65

Remarks: Set 230' of 8-5/8" surface casing w 180 sx cement  
  
Set 5 1/2" casing 3' off Botton w 125 sx cement

Formations

Clay & Sand	90'
Sand & Shale	115'
Red Bed	230'
Shale & Red Bed	1200'
Anhydrite	1250'
Lime & Shale	1910'
Shale & Lime Stks	2130'
Shale & Lime	3485'
Lime - Shale	3530'
Sand - Shale	3610'
Lime - Shale	3820'
Lime	3993'
Lime & Shale	4085'
Lime	4325'
Lime - Chert	4508'
Lime	4608'
Lime - Shale	4703'
Sand	4707'
Rotary Total Depth	4707'

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 7 1973  
CONSERVATION DIVISION  
Wichita, Kansas


We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

*Wilson Rains*  
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 30th day of November, 1965.

My commission expires:  
July 24, 1968



*Judith Caughlin*  
Judith Caughlin, Notary Public