

15-095-00609-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1970
CONSERVATION DIVISION
Wichita, Kansas
2-3-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drlg. Co.

Complete Address 705 4th Natl. Bank Bldg. Wichita, Ks 67202

Lease Name Bertholf C Well No. 1

Location SE/NW/SE Sec. 3 Twp. 30 Rge. 8 (E) (W)X

County Kingman Total Depth 4290

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling Inc.

Address Box 1082 Great Bend, Ks License No. 623

Operation Completed: Hour 9:30 AM Day 2 Month 2 Year 1970

The above well was plugged as follows:

257 ft of 8 5/8 surface pipe cemented with 250 sacks cement. 4245 ft
of 5 1/2 long string cemented with 150 sacks cement. Top perf 4165 ft.
Sand back to 4100 ft, and 5 sacks cement with bailer. 3505 ft of 5 1/2
pulled. Mud to 250 ft, 10 ft rock bridge, 25 sacks cement. Mud to
40 ft, 10 ft rock bridge. 10 sacks cement to surface.

I hereby certify that the above well was plugged as herein stated.

Signed L. Russell Beherstein
Well Plugging Supervisor

INVOICED

DATE 2/3/70

INV. NO. 1361-W