

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

W. S. E. V. E. Co.
 State of Kansas

AUG 3 1967
 8-3-67

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Larry Curtis of Duke Drilling Company has this date requested permission to plug the following described well:

Mr. James A. Allison guarantees payment of the plugging fee.

Operator's full Name: Allison & Black

Complete Address: 1415 Wichita Plaza, Wichita, Kansas

Lease Name: Goodwin Well No. # 1

Location: SE NW SW Sec. 3 Twp. 16 Rge. 11 (E)(W) W

County Barton Total Depth 3346 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Larry Curtis was instructed to plug the well as follows:

8 5/8" 330' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 30 sax

cement thru drill pipe. Mud to 320', set plug, & displaced 25 sax

cement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced

10 sax cement with Globe Cementing Company's pump truck, cementing

to base of cellar.

Very truly yours,

Don L. ...
 Conservation Division Agent