

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 6 1972
7-6-72
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lynn O. Duke of Duke Drilling Company has this
date requested permission to plug the following described well:

Mr. Duke Drilling Company guarantees payment of the plugging fee.

Operator's full Name: Duke Drilling Company, Inc.

Complete Address: 1105 Williams, Great Bend, Kansas 67530

Lease Name: Davidson "B" Well No. # 1

Location: NE NE NE Sec. 4 Twp. 16 Rge. 11 (E)(W) W

County: Barton Total Depth 3282 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. John Glenn was instructed to plug the well as follows:

8 5/8" csg. 502' Cwc. 4 1/2" csg. 2860'.

Sanded hole back to 2800' & dumped 4 sax cement with dump bailer.

Pulled pipe. Mud to 450', set 30' rock bridge, & displaced 6 yds.

Ready-mix Cement, cementing from 420' to base of cellar.

Very truly yours,

Don Lunsford
Conservation Division Agent