



15009-20863-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

December 14, 1974

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1974
12-27-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this

date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 816 Union Center, Wichita, Kansas 67202

Lease Name: Thill Well No. 1

Location: SE NW SE Sec. 5 Twp. 16 Rge. 11 (E) (W) X

County: Barton Total Depth 3330' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Rider was instructed to plug the well as follows:

Fill hole with mud. Push plug to 500' and pump 40 sacks

cement through drill pipe at 500'. Pump 25 sacks cement

through drill pipe at 250'. Push plug and 1/2 sack hulls to

40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,

William J. Roman
Conservation Division Agent