

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-22501-00-00
Spot: SWNE Sec/Twnshp/Rge: 8-22S-11W
4371 feet from S Section Line, 975 feet from E Section Line
Lease Name: SLEEPER Well #: 2
County: STAFFORD Total Vertical Depth: 3636 feet

Operator License No.: 6030
Op Name: AINSWORTH OPERATING CO.
Address: 4676 COMMERCIAL ST., SE #412
SALEM, OR 97302

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3644	0	WITH 150 SX CMT
SURF	8.625	276		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/21/2016 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 100# HULLS. PERFORATE AT 600'. PUMP 50 SX CMT IN & OUT WITH HULLS IN THE LAST 25 SX CMT. PERFORATE AT 300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2016 2:30 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

6/21/16: WELL WAS PERFORATED AT 600' & 300'. BOTTOM OF HOLE HAD SOME FILL TO 3450'. TBG WAS RUN IN HOLE TO 3450' PUMPED 50 SX CMT WITH 100# HULLS. PULL TBG OUT TO 600' & PUMPED 50 SX CMT WITH 50# HULLS IN LAST 25 SX CMT. GOOD CEMENT RETURNS UP 4 1/2" CASING. BACKSIDE VALVE OPENED & ANOTHER 75 SX CMT WAS PUMPED UP BACK SIDE WITH GOOD CEMENT RETURNS TO SURFACE. PULL TBG OUT OF HOLE & TOP OFF 4 1/2" WITH 35 SX CMT. 6/22/16: CMT FELL BACK. CMT LEVEL AT 80'. TOPPED OFF WITH REDI-MIX.

Perfs:

Top	Bot	Thru	Comments
3608	3616		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: TBG

District: 01

Signed

Ken Scofield
SA

(TECHNICIAN)

JS
JUL 29 2016

RECEIVED
JUL 22 2016
KCC DODGE CITY