

To: 1 090035
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,562 - 0000
SW NE NE, SEC. 14, T 24 S, R 33 W/E
4420 feet from S section line
710 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4058
Operator: American Warrior, Inc.
Name & Address P.O. Box 399
Garden City, KS 67846

Lease Name Garden City Well # 2
County Finney 129.02
Well Total Depth 2970 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1656

Abandoned Oil Well Gas Well X Input Well SMD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:45 p.m. Day: 17 Month: 12 Year: 19 90

Plugging proposal received from Chance Fulls
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 2969' w/375 sx cement, PBTD 2969', Perfs at 2859-67, 2848-54, 2823-33'
1st plug sand back to 2773' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 6 sx gel and 50 sx cement at stub,
3rd plug pump 50 sx cement at 400',
4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None
Operations Completed: Hour: 6:30 p.m. Day: 17 Month: 12 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 2775' and dumped 5 sx cement on top of
sand through bailer,
2nd plug pump 6 sx gel and 25 sx cement at 738',
3rd plug pulled to 400' and pumped 50 sx cement,
4th plug pulled to 40' and pumped 10 sx cement.

Cement circulated

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 738' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 1-8-91
INV. NO. 30393
12-17

Signed [Signature]
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
DEC 21 1990
CONSERVATION DIVISION
Wichita, Kansas
12-21-90