

1 110183

5-7

209

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-21, 101-0060

NE SE NW, SEC. 6, T 24 S, R 33 W/EX

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name H.J.B. Well # 1-6

Operator: BEREXCO INC.
Name & Address: 970 Fourth Financial Ctr.
Wichita, KS 67202

County Finney 159.25

Well Total Depth 4900 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1670

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor BEREDCO INC. License Number 5147

Address 401 E. Douglas, Wichita, KS 67202

Company to plug at: Hour: 5 a.m. Day: 7 Month: 5 Year: 19 92

Plugging proposal received from Gary Marshall

(company name) BEREDCO INC. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1550-1700'

1st plug at 2950' with 100 sx cement, 2nd plug at 1700' with 50 sx cement,

3rd plug at 850' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dick Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 a.m. Day: 7 Month: 5 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

2nd plug at 1700' with 50 sx cement,

3rd plug at 850' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by D & S.

If additional description is necessary, use BACK of this report.

I (XXXX/ did not) observe this plugging.

DATE 6-5-92

INV. NO. 35410

Signed James R. Ray (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION 5-15-92
MAY 15 1992
CONSERVATION DIVISION
Wichita, Kansas