

2 040228

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095- 20271-0001

SW/NE/SE, SEC. 33, T. 30 S, R. 7 W

1650 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6236

Lease Name Norris Well # 1

Operator: MTM Petro

County Harper

Name & Address Spiney, Ks. 67142

Well Total Depth 4400 143.00 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 8

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clark Corp. License Number 5105

Address Medicine Lodge

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Elmo

(company name) Clark Corp (phone)

were:

4 1/2 4400 Sand to 4324 & 4 sks.

Perf. 4374-76 3 hull 15 gel 135 sks.

Rec. 3300'

Plugging Proposal Received by Stan Marcotte
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1215 Day: 10 Month: 12 Year: 1985

ACTUAL PLUGGING REPORT The well was sandbed back to 4324' to cover the perforations and capped with 4 sks of cement. The 4 1/2" was shut off at 3300' and recovered from the hole. The top was plugged by squeezing thru the 10 3/4" surface pipe, 3 sacks of hulls, 15 sacks of gel and 135 sacks of cement.

Remarks: Allied Cement is # Headhake MX300 # SI 50 #
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 19 1985

I.V. NO. 11651

STATE CORPORATION COMMISSION

DEC 19 1985

CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
(TECHNICIAN)

12-19-85 RD

FORM CP-2/3
Rev. 01-84