

2-040554

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-095-30242-00-00

C SE NW, SECTION 36 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 6568 3300 FEET FROM S SECTION LINE
3300 FEET FROM E SECTION LINE

OPERATOR Kaiser Francis Oil Co.
NAME & P. O. Box 666
ADDRESS Ellinwood, KS 67526

LEASE NAME: Lechner #1
COUNTY: Kingman 153.41
WELL TOTAL DEPTH: 4722'

CONDUCTOR PIPE: " @ '
SURFACE CASING: 8-5/8" @ 231'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Chase, KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Millard Kelso
COMPANY NAME: Kelso Casing Pulling PHONE: _____

WERE: 35 sx @ 1250' - 35 sx @ 850' - circ 300' - 5-1/2"
4716' - sand to 4280' & 5 sx

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:00 DAY: 13 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT:
Bottom was sanded to 4280' & capped w/5 sx cmt - 5-1/2" was recovered from 2268' & pulled from hole - tub was run to 1250' w/35 sx cmt spotted - tub was pulled to 850' where 35 sx cmt was spotted - tub was pulled to 300' & circ to surface. 5-1/2" had holes - Hayes Well Service ran tub to plug.

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: Allied #6203 60/40 2% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

SEP 06 1990

DATE: _____

Steve Van Gieson
Steve Van Gieson (AGENT)

AUG 31 1990
8-31-90
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90

ML
INV. NO. 29217

7-13

104R

2-040544

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER:

C SE NW, SECTION 36 TOWNSHIP 30 RANGE 7W

OPERATOR LICENSE # 6568

FEET FROM S SECTION LINE

FEET FROM E SECTION LINE

OPERATOR Kaiser-Francis Oil Company

NAME & P. O. Box 666

ADDRESS Ellinwood, KS 67526

LEASE NAME: Leckner #1

COUNTY: Kingman

WELL TOTAL DEPTH: 4722' - 153.47

CONDUCTOR PIPE: " @ "

SURFACE CASING: 8-5/8" @ 231'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing

ADDRESS: Chase, Kansas LICENSE: 5060

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 12 MONTH: 7 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Jim

COMPANY NAME: _____ PHONE: _____

WHERE: Sand bottom to 4280' & 5 sx - 25 sx @ 1250' - 25 sx @ 850' 280' to 0 - 5-1/2" @ 4716' - perf 4330-40'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 16:00 DAY: 13 MONTH: 7 YEAR: 1990

ACTUAL PLUGGING REPORT: Sanded bottom to 4280' & 5 sx - Tubing was wash down the well bore to 1250' when 35 sx cmt spotted - tubing was then pulled to 850' & another 35 sx cmt was spotted - tubing was then pulled to 280' & cmt circ back to surface.

REMARKS: Allied #6203 60/40 2% gel

STATE CORPORATION COMMISSION
WICHITA, KANSAS

I DID OBSERVE THIS PLUGGING.

JUL 23 1990

Steve Van Gieson
Steve Van Gieson (AGENT)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90

INVOICED

DATE: 7-27-90

INV. NO. 28781

7-13 SEP 14 1990