

4-14 15-095-00765-00000
2-040762

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15- 9-11-58

SE NW SW, SECTION 3 TOWNSHIP 30 RANGE 8W

OPERATOR LICENSE # 5447 1650 FEET FROM S SECTION LINE
4290 FEET FROM E SECTION LINE

OPERATOR Oxy USA Inc.
NAME & 110 S. Main #800
ADDRESS Wichita, KS 67202

LEASE NAME: Bertholf Well# C-1
COUNTY: Kingman
WELL TOTAL DEPTH: 4282 139.16

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8 @ 405'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling

ADDRESS: Chase KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Don Herman

COMPANY NAME: Oxy USA Inc. PHONE: _____

WERE: Perf 4166'-4261' Sand to 4110 & 5sx
5-1/2 4306' Rec. 3000', 30sx 1250', 30sx
PBTD 4264' 810, circ cmt 450' 441

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 14:00 DAY: 14 MONTH: 4 YEAR: 1993

ACTUAL PLUGGING REPORT:
The Perfs were covered with sand to a top of 4110' &
capped with 5sx of cmt. The 5-1/2 was shot loose at
3000' and pulled to 1250' where 30sx of cmt was spotted.
The 5-1/2" casing was pulled to 800' where 30sx of cmt
was spotted. The 5-1/2" casing was pulled to 450'
where cmt was circ to surface.

5-27-93

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: Allied 60/40 2% gel 2946

MAY 27 1993

I DID OBERVE THIS PLUGGING.

INVOICED

Steve Van Gieson
Steve Van Gieson (AGENT)

CONSERVATION DIVISION
WICHITA, KS

DATE 6-3-93

REV. NO. 37813

FORM CP-2/3
REV. 3/90

4-14 JUL 22 1993