

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

8-28

2-040638

203
R

Rec'd
9-25-91

API NUMBER: 15-095-20,182 - 0000

NW NW SE, SECTION 3 TOWNSHIP 30 RANGE 8W

OPERATOR LICENSE # 6581 2310 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR Bison Energy
NAME & 9320 East Central
ADDRESS Wichita, KS 67206

LEASE NAME: Bertholf #C-2
COUNTY: Kingman
WELL TOTAL DEPTH: 4235'

CONDUCTOR PIPE: " @ ' 137.63

SURFACE CASING: 8-5/8" @ 212'

ABANDONED OIL WELL GAS WELL X INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE:

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Marvin Capps
COMPANY NAME: Shawnee Well Service PHONE:

WERE: 5-1/2" @ 4331'/170 sx - set CIBP@ 4100' & 2 sx - 35 sx
@ 1250' - 35 sx @ 850' - circ @ 262' - 4146'-4181'.

PLUGGING PROPOSAL RECEIVED BY:

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () NONE ()

COMPLETED: HOUR: 19:15 DAY: 28 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:

A CIBP was set @ 4100' & capped with 2 sx cmt - 5-
1/2" was shot loose @ 2804' and pulled to 1187.96'
where 35 sx cmt spotted - 5-1/2" pulled to 834' where
35 sx spotted - 5-1/2" pulled to 262' where cmt circ to
surf - remaining pipe pulled from hole & topped w/cmt -
recovered 2804' of 5-1/2".

REMARKS: B. J. Services #648739

IF I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 11-8-91

INV. NO. 33642

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

OW

8-28