

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-24727-00-00  
Spot: NESESE Sec/Twnshp/Rge: 4-16S-11W  
990 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: DAVIDSON B Well Number: 1  
County: BARTON Total Vertical Depth: 3364 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

Conductor Pipe: Size \_\_\_\_\_ feet: \$109.33  
Surface Casing: Size 8.625 feet: 360  
Production: Size \_\_\_\_\_ feet:  
Liner: Size \_\_\_\_\_ feet:

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2001 1:00 AM  
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC  
Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Order 150 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 11/14/2001 4:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3340' w/25 sxs. Anhydrite 730' - 750'.  
2nd. Plug at 750' w/25 sxs Surface pipe 360'.  
3rd. Plug at 410' w/50 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
12-21-01  
DEC 21 2001  
KCC WICHITA

INVOICED

Form CP-2/3

DATE 12-21-01  
WELL NO. 2002061087

DEC 19 2001