

6 030340

API NUMBER 15-009-23,783 ⁻⁰⁰⁰⁰ **R**

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 1, T. 16 S, R. 11 WE
3960 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 513B

Lease Name HOMOLKA Well # 1

Operator: COUGAR DRILLING CO. INC.

County BARTON 109.20

Name & Address 555 N. WOODLAWN SUITE 114

Well Total Depth 3360 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

6720B

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor COUGAR DRILLING CO. INC. License Number 45

Address 555 N. WOODLAWN SUITE 114 WICHITA, KANSAS 6720B

Company to plug at: Hour: PM Day: 16 Month: 11 Year: 19 84

Plugging proposal received from TOM CROWL

(company name) COUGAR DRILLING CO. INC. (phone) _____

were: ORDER 160 SX. 5950002 62GEL3 2 2 SX. CELLOFRANE - 18 5/8 WIPER PLUG.

CIRCULATE HOLE WITH NO LESS THAN 36 QTS. MUD WITH NO LOSS OF FLUID AND NO INCREASE OF FLUID FROM FORMATIONS. SPOT CEMENT MIX. WITH 4 1/2" DRILL PIPE KEEP DRILL HOLE FULL OF MUD.

SPOT FIRST PLUG AT 650' WITH 90 SX. OF CEM. MIX. SPOT SECOND PLUG AT 400' WITH

40 SX. OF CEM. MIX. SPOT THIRD PLUG AT 40' WITH CEM. MIX. ON TOP OF 8 5/8 WIPER PLUG.

CIRCULATE 10 SX. CEM. MIX. FROM BASE OF PATH HOLE WITH A JOINT OF PIPE AND 10 SX. IN MOUSE HOLE
ALLIED CEM. CO. Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:15 PM Day: 16 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT CIRCULATED HOLE WITH MUD SPOTTED 5950002 62GEL3 2 2 SX. CELLOFRANE

WITH 4 1/2" DRILL PIPE AT - 650' WITH 90 SX. - 400' WITH 40 SX. - 40' WITH WIPER PLUG

AND 10 SX. CIRCULATED 10 SX. IN PATH HOLE AND 10 SX. IN MOUSE HOLE

RECEIVED
STATE CORPORATION COMMISSION

DEC 03 1984
12-3-84

CONSERVATION DIVISION
Wichita, Kansas

Remarks: ELEV 1797 ANHY 633-653 NO ARB. NO TEST NO LOG.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 12-12-84

Signed Carl Goodrow
(TECHNICIAN)

INV. NO. 5944

11-30-84
3