

6 070605

10-3-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 009-24,249 -00-00
SE SE SE, SEC. 1, T 16 S, R 11 W/E
330 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3536

Lease Name John McFarland Well # 1

Operator: Ramco Drilling Service Inc.
Name & Address: Box 99
Belpre, Ohio 45714

County Barton Co. 115.05

Well Total Depth 3540 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 392

Bob Williamson or David Gocke

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co. Inc. License Number 5929

Address 620 Hubbard Box 823 Great Bend, Kansas 67530

Company to plug at: Hour: 3:00 PM Day: 3 Month: October Year: 19 87

Plugging proposal received from Pete Musgrove

(company name) Duke Drilling Co. Inc. (phone) 316-793-8366

were: 8 5/8" 392' S. P. cwc w/190 sks 60/40 Pozmix 2% Gel 3% Ca Cl. By Allied Cement.

Arbuckle at 3350' Elevation 1895', Anhydrite 740'. No circulation problems. Mud condition 44 vis; 9.2 weight; 11.5 water loss. Proposal 195 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 8 5/8" plug. Spot with drill stem, recondition hole (42 vis). Mud between all plugs. 25 sks at 3300'; 25 sks at 760'; 80 sks at 570'; 40 sks at 240'; Halls plug at 40' w/10 sks cement. 15 sks rat hole (circulate)

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 PM Day: 3 Month: October Year: 19 87

ACTUAL PLUGGING REPORT Ordered 195 sks 60/40 Pozmix 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem, reconditioned hole, heavy mud between all plugs.

1st plug 25 sks cement at 3300'. 2nd plug 25 sks cement at 760'.

3rd plug 80 sks w/1 Flocele at 570' 4th plug 40 sks at 240'

5th plug, Halls, plug at 40' w/10 sks cement. 15 sks in rat hole (circulate)

Cemented by Allied Cementing Co.

Remarks: (If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1987
10-23-87
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

observe this plugging.

DATE 10-26-87
INV. NO. 18673

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

FORM CP-2/3LR
Rev. 01-84