

4-071092

4-3

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-24,574-0000

C NE SE /4 SEC. 03, 16 S, 11 W
1980 feet from S section line
660 feet from E section line

Operator license# 31300 Lease Chase well # 1-3

Operator: Centrex Operating Company County Barton

Address: P.O. Box 52058 Well total depth 3452 feet
Tulsa, OK 74152-0058 Conductor Pipe: 0 inch @ 0 feet
J. Dustin Smith Surface pipe 8 5/8 Inch @ 403 feet

112.19

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Duke Drilling Company, Inc. License# 5929

Address: Great Bend, Kansas 67530

Company to plug at: Hour: 1:30P.M. Day: 3 Month: April Year: 94

Plugging proposal received from: Rich Wheeler

Company: Duke Drilling Company, Inc. Phone: 918-599-8128

Were: 8 5/8" - 403' S.P. cwc. w/180 sxs. 60/40 pozmix - 3% C.C. -
2% gel. By Halliburton. Elv. 1884' - Anhy. 722' - Arbuckle 3360' - No
circulation problems - Mud condition 48 vis. - 9 weight - 8 water loss.
Proposal 175 sxs. 60/40 pozmix - 6% gel - circulate hole - spot and
displace all cement through drill stem with havey mud between all plugs.
25 sxs. @ 3300' - 25 sxs. @ 730' - 100 sxs. @ 450' - 10 sxs. @ 40'.
15 sxs. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30P.M., Day: 3, Month: April, Year: 94

Actual plugging report: Duke Drilling ordered 175 sxs. 60/40 pozmix -
3% C.C. - 2% gel - circulated hole - spotted and displaced all cement
through drill pipe.

1st. plug at 3300' w/25 sxs. cement.
2nd. plug at 730' w/25 sxs. cement.
3rd. plug at 450' w/100 sxs. cement.
4th. plug at 40' w/10 sxs. cement.
15 sxs. in rathole (circulate)

Remarks: Cemented by Halliburton Services.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: 1884 GL

I did / did not [X] observe the plugging.

INVOICED
DATE 4-21-94
INV. NO. 40313

Marion J. Schmidt
(agent)
Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION
APR 07 1994
CONSERVATION DIVISION
Wichita, Kansas

4-3