

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-155-02187-0000

FILE NO. 5-43

LOCATION SW SE SE

SEC. 11 TWP. 23S RGE. 10W

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 7 Lease Albert Tonn

Operator The Carter Oil Co. Address Box 786, Great Bend, Kansas

Field Peace Creek County Reno

Total Depth 3755 Feet.

(Describe briefly the manner in which the well was plugged)

Dumped 6 sacks of cement at 3745 feet. Cement

filled to 3715 feet. Shot pipe loose at s064 feet.

Pulled pipe, mudded hole from 3715 feet to 285 feet.

Dumped 25 sacks of cement from 285 feet and filled

up to 235 feet. Finished filling surface pipe with

mud from 235 feet to 10 feet of top of surface and

finished with 8 sacks of cement at top of surface. *6-24-48*

Paul Dunbar
District Conservation Agent

Date March 17, 1948

PLUGGING
FILE SEC 11 T 23 R 15W
DICK PAGE 5 LINE 43

MAR 24 1948