

X
/

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NE 1/4

SEC. 4 TWP. 24 RGE. 24

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Schneider

Operator Fanhandle Eastern Pipe Line Address Box 979, Liberal, Kansas

Field _____ County Hodgeman

Total Depth 4783 Feet.

(Describe briefly the manner in which the well was plugged)

Well drilled to 4783 with rotary tools, hole was completely full of heavy rotary mud. Cement plug from 4658 to 4783' 50 sacks of cement pumped in hole by Halliburton. Rotary mud from 324 to 4658' Cement plug from 301 to 324' another cement plug from 0 to 17' . 324' of 10 3/4 surface pipe left in hole and steel cap welded on top of surface pipe, 4 feet below ground level.

RECEIVED
STATE CORPORATION COMMISSION

OCT 10 1951 10-10-51
CONSERVATION DIVISION
Wichita, Kansas
R. J. Phillips
District Conservation Agent

Date October 3, 1951

PLUGGING
FILE SEC 4 T 24 R 24
BOOK PAGE 114 LINE 7