

V
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1966
12-20-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Clinton Oil Company

Complete Address: 6810 West Highway 54, Wichita, Kansas

Lease Name Shriver Well No. # 1-V

Location NW NW SE Sec. 24 Twp. 30 Rge. 7 (E) (W) W

County Kingman Total Depth 4270'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 10:00AM Day 19th Month Dec. Year 1966

The Above well was plugged as follows:

280' of 8 5/8" surface pipe, cement circulatee with 200 sacks. Hole
was filled with drilling mud to 275', 1st cementing plug, bridged with
1 sack of dry cement and 1/2 sack of hulls on fluid at 275', and cemented
with 24 sacks. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlie Elving
Well Plugging Supervisor

DATE 12/20/66
INV. NO. 4495-W