

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1964
11-30-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Brown of Aylward Drilling Co. has this

date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.Operator's full Name: Aylward Drilling Co.Complete Address: Wichita, KansasLease Name: Borieson Well No. # 1Location: C SE SE Sec. 24 Twp. 24S Rge. 24 (E/W)County Hodgeman Total Depth 4870' Oil Well XGas Well Input Well SWD Well D & A X Lost Hole Mr. Brown was instructed to plug the well as follows:8 5/8"-352' Circulated w/cement.Mud 4870' to 700' Spotted 25 Sax. cement 700' to 625'Mud 625' to 325' Spotted 25 Sax. cement 325' to 250'Mud 250' to 40' Plug, Hulls, 10 Sax. cement 40' to 03 Sax. cement in rat hole.

Very truly yours,

Hugh Ross
Conservation Division Agent