



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

July 2, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)
15-155.20529-0000

RECEIVED
STATE CORPORATION COMMISSION

JUL 14 1978
7/14/78
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Elmer Zimmerman of Woodman-Lannitti Drilling Co. has this date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: Brougher Oil Company

Complete Address: P.O. Drawer 1367, Great Bend, Kansas 67530

Lease Name: Maecel Well No. 1

Location: C 5/2 SE NW Sec. 20 Twp. 23 Rge. 9 (W) X

County: Reno Total Depth 3930' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:

Fill hole with mud. Pump 40 sacks cement through drill pipe at 500'. Pump 25 sacks cement through drill pipe at 240'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rat hole and cement with 2 sacks cement.

8 5/8 - 254' - 200 sacks

Very truly yours,


Conservation Division Agent