



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15.063.00123.00.01

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 12 1971
CONSERVATION DIVISION
Wichita, Kansas
1-12-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Knight Csg. Pulling Co., Inc. has this
date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: California Time Petroleum Company,

Complete Address: 9460 Wilshire Boulevard, Beverly Hills, California.

Lease Name: Jacka Well No. 1

Location: CSE-SE Sec. 8 Twp. 15 Rge. (E)(W) 26
RTD-4300'

County: Gove Total Depth 4178' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

172'--8 5/8" Surface casing, cement circulated.

4175'--4 1/2" Production casing cemented on bottom with 150 Sx. No plug
back nor perforations indicated. (No attempt to salvage 4 1/2" casing).

Squeeze well thru 4 1/2" casing initially with 20 Sx. cement then 22 sacks
gel and finally with 55 Sx. cement. Squeeze well thru annulus with 5
sacks hulls then 15 sacks gel and finally 135 Sx. cement.

Very truly yours,

H. L. Nichols
Conservation Division Agent