



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

15.063.20150.00.00

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 1 - 1972  
12-1-72  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company has this  
date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Jilg Well No. A-1

Location: 150' NW of CNW-NE Sec. 1 Twp. 14 Rge. (E)(W)30

County: Gove Total Depth 4390' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

252'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1075' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent