

State of Kansas



ROBERT B. DOCKING Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 DALE E. SAFFELS Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

July 11, 1968

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUL 15 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Home Stake Production Company

Complete Address: P.O. Box 68, Burrton, Kansas 67020

Lease Name: Vansickle Well No. W-22

Location: App. C NW Sec. 10 Twp. 24 Rge. 4 (E) (W) X

County: Reno Total Depth 3369 Oil Well     

Gas Well      Input Well X SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3300' and cement with 3 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 25 sacks cement. Fill hole with mud to 30'. Set

rock bridge from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent