



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 JUL 23 1968
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

July 13, 1968

7-23-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Home Stake Production Company

Complete Address: P.O. Box 68, Burrton, Kansas 67020

Lease Name: Vansickle Well No. W-20

Location: NE NW NW Sec. 10 Twp. 24 Rge. 4 (E)(W) X

County: Reno Total Depth 3375' Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:


Fill hole with sand to 3300' and cement with 3 sacks.

Fill hole with mud to 310'. Set rock bridge from 310' to 300' and

cement hole with 25 sacks. Fill hole with mud to 30'. Set rock bridge

from 30' to 20' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent