



RP

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 30 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Holmstrom of K.N.N.G. has this

date requested permission to plug the following described well:

Mr. Holmstrom guarantees payment of the plugging fee.

Operator's full Name: Kansas-Nebraska Natural Gas Co., Inc.

Complete Address: 300 N. St. Joseph Ave., Hastings, Nebraska

Lease Name: Eichorn Well No. 1

Location: G W/2 Sec. 18 Twp. 24 Rge. 31 (E) (W)

County: Finney Total Depth 2687' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Holmstrom was instructed to plug the well as follows:

8 5/8" to 372' circulated w/ cement. 5 1/2" to 2683' cemented.

Top perforations 2632' Plug bottom w/ 25 sacks cement

Top of cement 2414' Mud 2414' to 400'

Spot 50 sacks cement 400' to 250' Mud 250' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves  
 Conservation Division Agent