

11-7

4-060768

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167-21,076 *0000*

W2 SW SE /4 SEC. 35, 15 S, 14 W
660 feet from S section line
2310 feet from E section line

Operator license# 5184

Lease: Batt Well # 4

Operator: Shields Oil Producers, Inc.

County: Russell 115.99

Address: Shields Building
Russell, Kansas 67665

Well total depth 3569 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 248 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Co Tools License# -

Address:

Company to plug at: Hour: 8:30 A.M. Day: 7 Month: November Year: 1995

Plugging proposal received from: Marvin Ratts

Company: Shields Oil Producers, Inc. Phone: 913-483-3141

Were: Order 170 sxs 60/40 posmix - 10% gel and hulls and 15 sxs gel.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00 A.M. Day: 7 Month: November Year: 1995

Actual plugging report: 8 5/8" to 248 w/150 sxs. 5 1/2" to 3385' w/75 sxs. Stage tool at 900' cemented with 150 sxs. Tied onto production casing and pumped 30 sxs cement with 300# hulls, 15 sxs gel and 135 sxs cement with 100# hulls. Max. P.S.I. 1200#. S.I.P. 1000#. Tied onto annulus and pumped 25 sxs cement. Max. P.S.I. 500#. S.I.P. 400#. Pressure locked up.

KANSAS CORPORATION COMMISSION

11-17-95
NOV 17 1995

CONSERVATION DIVISION
WICHITA KS

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 1885 GL

INVOICED

I did[] / did not[X] observe the plugging.

[Signature]
DH (agent)
Form CP-2/3

DATE 11-20-95

INV. NO. 44061 11-7 JAN 17 1996