

X  
4-090558

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-167-20,995-00-<sup>02</sup>  
NE NE SW /4 SEC. 26, 13 S, 15 W  
2310 feet from S section line  
2970 feet from E section line

Operator license# 7054

Lease Polcyn Twin Well # 3

Operator: Doonan & Sons, Inc.

County: Russell

Address: P.O. Box 1286  
Great Bend, Kansas 67530

Well total depth 3385 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 250 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 467 - Chase, Kansas 67524

Company to plug at: Hour: 1:00 P.M. Day: 29 Month: January Year: 1997

Plugging proposal received from: Mike Kelso/James Ray

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 190 sxs 60/40 posmix - 10% gel - 13 sxs gel - hulls.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 4:30 P.M., Day: 29, Month: January, Year: 1997

Actual plugging report: 8 5/8" to 250'. 5 1/2" to 3380'. T.O.C. 2660'. Perfs at 2955' - 3027'. Tied onto production casing. Pumped 40 sxs cement with 300# hulls, 13 sxs gel with 200# hulls and 75 sxs cement and displaced to 550'. Shot casing at 500' and was free. Pumped 35 sxs cement. Pulled casing to 150' and circulated cement with 40 sxs. Used 190 sxs cement total.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD  Any plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: 1889 GL

I did[  ] / did not[  ] observe the plugging.

Ed Ackerman  
DH (agent)  
Form CP-2/3