

6-9 4-010271

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-167-22,388 -00-00

NE SW SE /4 SEC. 18, 13 S, 15 W
990 feet from S section line
1650 feet from E section line

Operator license# 31925

Lease: Schuckman-Nowak 'B' Well # 2

Operator: Quality Well Service

County: Russell 109.82

Address: 249 E. Beth Drive
Sterling, Kansas 67579

Well total depth 3379 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 713 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67601

Company to plug at: Hour: 11:00A.M. Day: 9 Month: June Year: 1997

Plugging proposal received from: Richard McIntyre

Company: Quality Well Service Phone:

Were: Same as below.

RECEIVED
KANSAS
CORP. (00:00)
1997 JUN 11 P 1:24
6-11-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 1:30 P.M., Day: 9, Month: June, Year: 1997

Actual plugging report: Sanded to 3035' and dumped 5 sxs. Shot off pipe at 2227'.
Pulled to 1600' and pumped 110 sxs 60/40 - 10% gel with 300# hulls. Pulled to 1000' and
pumped 40 sxs with 200# hulls. Pulled to 500' and pumped 30 sxs. Pulled to 150' and
circulated with 30 sxs.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X. Elevation: GL

I did [X] / did not [] observe the plugging.

Carmond
(agent)
Form CP-2/3

INVOICED

DATE 6-16-97

INV. NO. 48342

6-9