

4-060856

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

3-15

API Number: 15-167-20888-00-00

SW SE SW \_\_\_\_\_ / 4 SEC. 04, 12 S, 15 W  
330 feet from S section line  
1650 feet from E section line

Operator license# 5184

Lease: Eulert "B" Well # 6

Operator: Shields Oil Producers, Inc.

County: Russell

Address: Shields Building  
Russell, Kansas 67665

Well total depth 2450 <sup>79.62</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 535 feet

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: P.O. Box 209 - Chase, Kansas 67524

Company to plug at: Hour: 3:00 P.M. Day: 15 Month: March Year: 1996

Plugging proposal received from: Mike Kelso/Manny

Company: Mike's Testing & Salvage, Inc. Phone: 316-938-2943

Were: Order 180 sxs 60/40 posmix - 10% gel and hulls.  
Plug while pulling casing.

RECEIVED  
KANSAS CORP. 2011  
APR 12 A 11:18  
4-12-96

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]


Completed: Hour: 5:00 P.M., Day: 15, Month: March, Year: 1996

Actual plugging report: 8 5/8" to 535' w/375 sxs. 4 1/2" to 2449' w/75 sxs. Perfs. from 2357' - 2361'. Sanded to 2300' and spotted 4 sxs cement with dump bailer. Shot casing loose at 1815' and pulled to 1375'. Mixed and pumped 65 sxs cement with 300# hulls. Pulled casing to 775' and pumped 40 sxs cement with 200# hulls. Pulled casing to 275' and circulated cement with 70 sxs. Pulled casing and topped with 5 sxs cement.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD  BAD \_\_\_\_\_ Anhy.plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES , CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING . Elevation: 1690 GL

I did [ ] / did not [ X ] observe the plugging.

  
PK (agent)

Form CP-2/3

**INVOICED**  
DATE 4-16-96  
INV. NO. 45304