

15-083-10096-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 63  
NW/4 Sec. 26, T 22 S, R 22 W/E  
1980 feet from N/E section line  
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hann Well # B-2

Operator: City Service Oil Co  
Name & Address Box 38  
Bazine, Kans 67561

County Hodgman  
Well Total Depth 4425 feet \$ 14381  
Production Production  
Conductor Pipe: Size 5 1/2" feet 4420'  
Surface Casing: Size 8 3/8" feet 1312'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hess County Well Service License Number 7527

Address R.R. #1 So. Kansas Ave, Box 9, Hess City, Kans 67560

Company to plug at: Hour: 8:30 AM Day: 17 Month: 6 Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob Walters

(company name) City Service Oil Co (phone) \_\_\_\_\_

were: 1st plug shot 5 1/2" off at 1350' w/ hole full of heavy mud & pumped 35 sks cement @ 1350'. 2nd pulled 5 1/2" to 750' & pumped 50 sks cement. 3rd plug pulled pipe to 40' & pumped 30 sks cement, filling hole to 0'. Halliburton cementing accomplished the cementing of common cement.  
Signed J. A. Luthie  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 4:30 P.M. Day: 17 Month: 6 Year: 1983

ACTUAL PLUGGING REPORT \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

JUN 21 1983 6-21-83

CONSERVATION DIVISION  
Wichita, Kansas

6-16-83

Remarks: We pumped heavy jell into 5 1/2" till pressure built to 1200#. Then pumped into annularise w/ 750# pressure & topped out at 800#. Bled pressures off 6-17-83 shot pipe off & annularised. Mr. Don Ubel gave the plugging procedure to Mr. Luthie to give to Mr. Bob Walters

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

Signed J. A. Luthie ✓  
(TECHNICIAN)

FORM CP-2/3  
Rev. 9-82

INVOICED  
DATE 6-24-83  
INV. NO. 4643-W