

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-13 API NUMBER: 15-155-20,793-0006

NE NE SE, SECTION 7 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 4767 2310' FEET FROM S SECTION LINE
OPERATOR RITCHIE EXPLORATION INC. 330' FEET FROM E SECTION LINE
NAME & ADDRESS 125 NORTH MARKET, SUITE 1000
WICHITA, KS 67202
LEASE NAME: C. MILLER "A-P" #2
COUNTY: RENO
WELL TOTAL DEPTH: 3360' 109.20
CONDUCTOR PIPE:
SURFACE CASING: 8 5/8" @ 433'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE INC.
ADDRESS: P.O. BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 13 MONTH: 9 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: BENNIE DILLS
COMPANY NAME: RITCHIE EXPLORATION INC PHONE: (316) 793-2525
WERE: SAND TO 3300' AND TOP WITH 5 SACKS OF CEMENT. SHOOT PIPE OFF. PULL PIPE TO 700' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 480' AND CIRCULATE CEMENT TO THE SURFACE.

5 1/2" CASING AT 3357
OPEN HOLE FROM 3357' TO 3360'

RECEIVED
STATE CORPORATION COMMISSION

SEP 25 1996 9-25-96

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART () CONSERVATION DIVISION
Wichita, Kansas

COMPLETED: HOUR: 16:30 DAY: 13 MONTH: 9 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED TO 3285' AND TOPPED WITH 5 SACKS OF CEMENT. (DAVE WERTZ WITNESSED BOTTOM PLUG). PULLED PIPE APART AT 958'. PULLED PIPE TO 673' AND SPOTTED 35 SACKS OF CEMENT. PULLED PIPE TO 486' AND CIRCULATED 160 SACKS OF CEMENT TO THE SURFACE.
RECOVERED 958' OF 5 1/2" CASING.

REMARKS: USED 60/40 POZ 4% GEL ALLIED #4151

INVOICED

SEP 26 1996

DATE

INV. NO. 46623

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
MICHAEL R. WILSON