

1-23

2-100683

229
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-155-20,872-0000

SE NE SE, SECTION 7 TOWNSHIP 24 RANGE 4W

OPERATOR LICENSE # 4767 1800 FEET FROM S SECTION LINE
660 FEET FROM E SECTION LINE

OPERATOR Ritchie Exploration, Inc.
NAME & 125 N. Market, #1000
ADDRESS Wichita, KS 67202

LEASE NAME: H. Bogner #P-3
COUNTY: Reno
WELL TOTAL DEPTH: 3365' 109.36

PIPE: 5-1/2" @ 3359'/100 sx
SURFACE CASING: 8-5/8" @ 493'/275 sx

ABANDONED OIL WELL GAS WELL INPUT WELL SUD D&A

OTHER WELL AS HEREINAFTER INDICATED: open hole 3359-65'

PLUGGING CONTRACTOR: Kelso Casing Pulling
ADDRESS: Box 347, Chase, KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 23 MONTH: 1 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Bennie Dill
COMPANY NAME: Kelso Casing Pulling PHONE: 316-938-2943

WERE: Pump thru swedge 3 sx hulls, 60 sx 60/40 2% gel cmt,
7 sx gel, 3 bbls water to sack - 8-5/8" plug w/40 sx
cement. Bottom - Sand to 3310' & 5 sx cmt - shoot & pull 5-1/2"

PLUGGING PROPOSAL RECEIVED BY: M. L. Korphage

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 11:30 DAY: 23 MONTH: 1 YEAR: 1991

ACTUAL PLUGGING REPORT:
Pumped thru swedge 3 sx hulls, 60 sx cmt, 7 sx gel -
8-5/8" plug with 40 sx cmt - fell 38' - filled with cmt
to top. Bottom - Sanded to 3310' & 5 sx cmt - shot & pulled
2116' of 5-1/2".

REMARKS: Allied #1230 60/40 2% Oper. 100# SI 50#

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 2-25-91

INV. NO. 30870

J. L. Sanders
J. L. Sanders (AGENT)

CONSERVATION DIVISION
Wichita, Kansas

FEB 22 1991 2-2291

FORM CP-2/3
REV. 3/90

ow