

To: 1 090671
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

15-055-00828-0000
API NUMBER 15- Spud date 11/4/61

C SW , SEC. 21 , T 24 S, R 31 W/E
1320 feet from S section line
3960 feet from E section line

4-23
TECHNICIAN'S PLUGGING REPORT

Operator License / 5317

Lease Name Lee Kisner Unit Well # 1

Operator: Continental Energy

County Finney 87.10

Name:
Address P.O. Box 918

Well Total Depth 2680 feet

Garden City, KS 67846-0918

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 23 Month: 4 Year: 19 96

Plugging proposal received from Richard McIntyre

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 4 1/2" at 2676' w/75 sx cement, PBD 2674', Perfs at 2660-73'

1st plug set CIBP at 2600' with 2 sx cement on top,

2nd plug perforate at 1200' with 80 sx cement,

3rd plug at cut off with 50 sx cement,

4th plug at 340' with 50 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 23 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2600' with 2 sx cement on top,

2nd plug perforated casing at 1200' and pumped in 80 sx cement and 10 sx gel,

3rd plug shot casing at 600' and pumped 30 sx cement,

4th plug pulled to 380' and circulated 80 sx cement to surface. Stayed full.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 600' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE APR 29 1996

INV. NO. 45464
4-23

4-25-96
1996 APR 25
RECEIVED
KANSAS CORP
SIGNED [Signature] (TECHNICIAN)