

To: 1 051524
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-30 API NUMBER 15-055-20,603-0000 150
NE SW SE, SEC. 13, T. 24 S, R. 33 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5317

Operator: Continental Energy
Name & Address: P.O. Box 918
Garden City, KS 67846

990 feet from S section line
1650 feet from E section line
Lease Name Corley Well # 1
County Finney 164.77
Well Total Depth 5070 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1663

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Continental Energy License Number 5317
Address P.O. Box 918, Garden City, KS 67846

Company to plug at: Hour: 9 a.m. Day: 30 Month: 1 Year: 19 92

Plugging proposal received from Kevin Wiles

(company name) Continental Energy (phone) 316-276-8710

were: 5 1/2" at 3038' w/425 sx cement, PBTD 2997', Perfs at 2851-61, 2838-44, 2825-32'

TOC 2100'

1st plug pump 2 sx hulls and fill 5 1/2" with cement,

2nd plug fill 8 5/8" X 5 1/2" annulus to 1663' w/cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 30 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 30 sx cement to 2725'. Plug slipped out of pipe. Pumped 3 sx hulls and 20 sx cement to 2600'.

Spotted plugs through casing:

2nd plug at 1850' with 50 sx cement,

3rd plug at 700' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1619' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-12-92

INV. NO. 34515

Signed Richard W. Lucas
(TECHNICIAN)