

R

To: 1051641 4-28  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
203 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-055-00823-0000  
15- Drilled completion date 3/10/61  
C NW, SEC. 16, T. 24 S, R. 31 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3871  
Operator: Hugoton Energy Corporation  
Name & Address: 229 E. William, Ste. 500  
Wichita, KS 67202

1320 feet from N & section line  
1250 feet from W & section line  
Lease Name Biernacki Well # 1-16  
County Finney 88.23  
Well Total Depth 2715 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 9 a.m. Day: 28 Month: 4 Year: 19 93

Plugging proposal received from Manny Boatright  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Work: 5 1/2" at 2709' w/300 sx cement. PBTD 2708', Perfs at 2664-72'  
1st plug sand back to 2610' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 50 sx cement at 1920'. 3rd plug pump 80 sx cement at 1150',  
4th plug pump 50 sx cement at 320'. 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:05 p.m. Day: 28 Month: 4 Year: 1993

ACTUAL PLUGGING REPORT 1st plug sanded back to 2610' and dumped 5 sx cement on top of sand  
through bailer. Circulated hole with gel and then spotted plugs through casing:  
2nd plug pumped 80 sx cement at 1100',  
3rd plug pumped 50 sx cement at 320',  
4th plug pumped 10 sx cement at 40'.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 30 1993  
4-30-93  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Western. Recovered 1159' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

1 (copy) ~~XXXXXXXXXX~~ observe this plugging.

DATE 5-11-93  
INV. NO. 37665

Signed Richard M. Lacey  
(TECHNICIAN)

RML