

To: 1 031246
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200, COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-10

API NUMBER 15- 055-20,120-0000

App. C.E/2, SEC. 18, T 24 S, R 31 W/E

2640 feet from S section line
1270 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5317

Lease Name Eichorn Well # 1

Operator: Continental Energy
Name & Address: P.O. Box 918
Garden City, KS 67846

County Finney
Well Total Depth 2740 89.05 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Rogers Well Service License Number 31125
Address: P.O. Box 918, Garden City, KS 67846

Company to plug at: Hour: 10 a.m. Day: 10 Month: 9 Year: 1993

Plugging proposal received from Russell Freeman
(company name) Continental Energy (phone) 316-276-3710

work: 4 1/2" at 2737' w/650 sx cement, PBTD 2722', Perfs at 2652-64'
1st plug spot 25 sx cement at 1452',
2nd plug spot 90 sx cement at 1198', circulate cement to 0',
3rd plug squeeze 4 1/2" with 35 sx cement,
4th plug pump 25 sx cement down 8 5/8" annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 10 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug spot 25 sx plug at 1452',
2nd plug spot 90 sx cement at 1198', circulated cement to surface,
3rd plug squeezed 4 1/2" with 35 sx cement,
4th plug pumped 25 sx cement down 8 5/8" annulus. Cement surfaced outside surface pipe at 300#.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

RECEIVED STATE CORPORATION COMMISSION

9-14-93 SEP 14 1993

If additional description is necessary, use BACK of this form.)

(did / observe this plugging.

CONSERVATION DIVISION Wichita, Kansas

Signed Steve Durrant (TECHNICIAN)

INVOICED
DATE SEP 14 1993
INV. NO. 38643