

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20121-00-00
Spot: CSE Sec/Twnshp/Rge: 19-24S-31W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease/Unit Name: MORRIS Well Number: 1
County: FINNEY Total Vertical Depth: 2710 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

Production Casing Size: 4.5 feet: 2710 WITH 650 SX CMT
Surface Casing Size: 8.625 feet: 379 WITH 250 SX CMT

\$ 88.08

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/09/2003 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KEVIN WILES SR. Company: AMERICAN WARRIOR Phone: (620) 272-4996

Proposed Plugging Method: PUMP 400# HULLS. FILL CASING WITH CMT. PUMP 50 SX CMT DOWN BACKSIDE IF NEEDED.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/09/2003 12:45 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 2703'. PERFS AT 2628-38'. ANHYDRITE DEPTH 1965'. SET CIBP @ 2570' WITH 2 SX CMT. PRESSURE TESTED CASING TO 1000#. PRESSURE HELD. PERFORATED AT 1406-07.5'. PRESSURED UP TO 2500# WOULD NOT GO. PERFORATED AT 1485'. TOOK INJECTION RATE 1600# 2 BPM. PUMPED 200# HULLS MIXED IN FIRST PART OF CMT. PUMPED 100 SX CMT. MAXIMUM PRESSURE 1600#. SHUT IN AT 0#. CMT STAYED AT SURFACE. PUMPED 25 SX CMT DOWN 8 5/8" X 4 1/2" ANNULUS. SHUT IN AT 500#.

RECEIVED
APR 18 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED
DATE 4-21-03
TEL. NO. 2003061428

Form CP 2/3