

1 070035

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,223-0000

C SW NE, SEC. 2, T 24 S, R 25 W/K
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Tubbs Well # 1

Operator: Falcon Exploration, Inc.

County Hodgeman 160.55

Name &

Address Kansas State Bank Building, # 1531
Wichita, KS 67202

Well Total Depth 4940 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling License Number 5104

Address P. O. Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 1:00 am Day: 24 Month: October Year: 19 85

Plugging proposal received from Martin Miller

(company name) Blue Goose (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe
Elevation NA
Anhydrite 1682-1717

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 70 sx cement

3rd plug 30' below the base of the surface pipe with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement
Plugging Proposal Received by Dan Goodrow

Plugging Operations attended by Agent?: All Part X None
(TECHNICIAN)
Richard W. Lacey saw part

Operations Completed: Hour: 3:45 am Day: 24 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1710' with 50 sx cement, 2nd plug at 810' with 70 sx
cement, 3rd plug at 330' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10
sx cement.

10-28-85 RECEIVED STATE CORPORATION COMMISSION

OCT 29 1985

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(if additional description is necessary, use BACK of this form.)

Richard W. Lacey saw part
(if desired, observe this plugging.)

CONSERVATION DIVISION
Wichita, Kansas

Signed Dan Goodrow
(TECHNICIAN)

DATE OCT 29 1985

INV. NO. 10774
10-24

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL

CARD MUST BE SIGNED

Starting Date: October 15, 1985

API Number 15- 08.3-21,223-0000

OPERATOR: License # 5316
Name: Falcon Exploration Inc.
Address: Suite 1531 KSB Bldg.
City/State/Zip: Wichita, KS 67202
Contact Person: Mike Mitchell
Phone: (316)262-1378

Location: SW NE, Sec 2, Twp 24, S, Rge 25
3300 Ft North from Southeast Corner of Section 1980
1980 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5104
Name: Blue Goose Drilling
City/State: Great Bend, KS

Nearest lease or unit boundary line: 1980 feet
County: Hodgeman
Lease Name: Tubbs Well# 1
Domestic well within 330 feet: [] yes [X] no
Municipal well within one mile: [] yes [X] no

Well Drilled For: Well Class: Type Equipment:
[X] Oil [] Swd [] Infield [X] Mud Rotary
[X] Gas [] Inj [] Pool Ext [] Air Rotary
[] GWFO [] Expl [X] Wildcat [] Cable

Depth to Bottom of fresh water: 75 feet
Lowest usable water formation: Dakota
Depth to Bottom of usable water: 425 475 feet
Surface pipe by Alternate: [] 1 [X] 2
Surface pipe to be set: 250 feet
Conductor pipe if any required: feet
Ground surface elevation: feet MSI
This Authorization Expires: 4-10-86
Approved By: 10-10-85

If OWFO: old well info as follows:

Operator:
Well Name:
Comp Date: Old Total Depth:
Projected Total Depth: 4900 feet
Projected Formation at TD: Mississippi
Expected Producing Formations: LKC, Miss

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date: 10-10-85 Signature of Operator or Agent: [Signature] Title: President

Form C-1 4/84

WW

Mov'd in 10-16-85

270' S.P.

285' G.E.

PUSHER: Martin Miller
TD: 4940 FORMATION MISS
SURFACE PIPE: 8 5/8 303
ANHYDRITE: 1662-1717 ELEVATION

STARTING TIME & DATE: 3
COMPLETION TIME & DATE: 10/24/85 3:45 am

1st PLUG @ 1210 FT. WI 50 SX

2nd PLUG @ 810 FT. WI 70 SX

3rd PLUG @ 330 FT. WI 40 SX

4th PLUG @ 40 FT. WISP+16 SX

RAT HOLE CIRCULATION WI 10 SX

MOUSE HOLE CIRCULATION WI SX

WATER SUPPLY WELL PLUGGED WI SX

TECHNICIAN: Richard Wilacey saw part

CEMENT COMPANY: Halliburton 60/40

Base Any

Base Cheyenne

130' below sp.

40-0 plug + cement

10 Rat

RECEIVED STATE CORPORATION COMMISSION 10-28-85 OCT 28 1985