

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19276-00-00
Spot: SESENWSW Sec/Twnshp/Rge: 34-29S-10E
1367 feet from S Section Line, 3981 feet from E Section Line
Lease Name: ELDEN BURKE Well #: 20
County: ELK Total Vertical Depth: 1364 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: P.O. BOX 725 128 N. PINE
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1350		175 SX
SURF	7	1338		0 SX

Well Type: EOR UIC Docket No: E02730.3 Date/Time to Plug: 04/11/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MAURICE PERKI Company: Phone: (620) 374-2000

Proposed Plugging Method: Both 7" and 4 1/2" casing cemented to surface. Run in with 1" tubing, spot 50ft cement on bottom, pull up and spot 50ft cement plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 04/12/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1300' gelled hole and spotted 5 sack plug. Pulled up to 900' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 68 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1350	1364		


RECEIVED
KCC DIST # 3
JUL 26 2016
CHANUTE, KS
DS

Remarks: WELL WAS ON COMPLIANCE AGGEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUL 29 2016

CONSERVATION DIVISION
WICHITA, KS

JUL 29 2016
cc uic

Form CP-2/3