

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19231-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 34-29S-10E
1025 feet from S Section Line, 4287 feet from E Section Line
Lease Name: ELDEN BURKE Well #: 5
County: ELK Total Vertical Depth: 1387 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: P.O. BOX 725 128 N. PINE
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.627	1354		0 SX
SURF	8	775		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MAURICE PERKINS Company: _____ Phone: (620) 374-2000

Proposed Plugging Method: This is old cable tool hole with open hole completion, there are no records other than driller's log. Run in with 1" tubing to TD, spot 50ft cement plug, pull 1" tubing, perforate at 1000ft and 500ft, run in with 1" tubing and spot 50ft cement plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 04/15/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1300' gelled hole and spotted 5 sack plug. Pulled 1" and perforated 6" and 8" casing at 900' and 550'. Ran 1" to 900' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 161 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1354	1387		

RECEIVED
KCC DIST # 3
JUL 26 2016
CHANUTE, KS
DS

Remarks: WELL WAS ON COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed _____

DS

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

JUL 29 2016

CONSERVATION DIVISION
WICHITA, KS

JUL 29 2016

Form CP-2/3