

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19227-00-00
Spot: NENWNESW Sec/Twnshp/Rge: 34-29S-10E
2358 feet from S Section Line, 3574 feet from E Section Line
Lease Name: ELDEN BURKE Well #: 1
County: ELK Total Vertical Depth: 1376 feet

Operator License No.: 5177
Op Name: SUERTE OIL COMPANY
Address: P.O. BOX 725 128 N. PINE
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1337		0 SX
SURF	7	790		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2016 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: MAURICE PERKINS Company: _____ Phone: (620) 374-2000

Proposed Plugging Method: We have no records of the amount of cement used for surface casing and production casing. Run 1" to TD, gel hole, spot 50' plug of cement on bottom, pull 1", perforate at 1000ft and 500ft, run 1" back in and spot 50ft plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2016 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1320' gelled hole and spotted 5 sack plug. Pulled 1" and perforated 4.5" and 7" at 900' and 550'. Ran 1" to 900' and spotted 5 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 150 sacks of cement were used to plug this well.

Perfs:

RECEIVED
KCC DIST # 3
JUL 26 2016
CHANUTE, KS

DS

Remarks: WQELL WAS ON COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed _____

Duane A Sims

(TECHNICIAN)

JUL 29 2016

Received
KANSAS CORPORATION COMMISSION

JUL 29 2016

CONSERVATION DIVISION
WICHITA, KS