

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-21394-00-00  
Spot: NWSWSWNW Sec/Twnshp/Rge: 34-29S-10E  
3012 feet from S Section Line, 5110 feet from E Section Line  
Lease Name: DUNKELBERGER Well #: 32  
County: ELK Total Vertical Depth: 2045 feet

Operator License No.: 5177  
Op Name: SUERTE OIL COMPANY  
Address: P.O. BOX 725 128 N. PINE  
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1380		
CIBP		1440		
PROD	4.5	2042		0 SX
SURF	8	0		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/19/2016 12:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: MAURICE PERKINS Company: \_\_\_\_\_ Phone: (620) 374-2000

Proposed Plugging Method: CBL shows 4 1/2" casing cement top at approx. 1350ft, no record of surface casing amount or cement data. Run in with 1" tubing to 1380ft(cibp), gel hole, spot 50ft cement plug, pull 1" out of hole, perforate at 1000ft and 500ft, run in with 1" tubing and spot 50ft cement plug at 1000ft, pull to 500ft and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/20/2016 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1350' gelled hole and spotted 5 sack plug. Pulled 1" and perforated casing at 900' and 550'. Ran 1" to 900' and spotted 12 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 137 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
2026	2035		
1420	1424		
1351	1368		

RECEIVED  
KCC DIST # 3  
JUL 26 2016  
CHANUTE, KS

DS

Remarks: WELL WAS ON COMPLIANCE AGREEMENT SIGNED BY OPERATOR.

Plugged through: TBG

District: 03

Signed

*Duane Sims*

(TECHNICIAN)

JUL 29 2016

Received  
KANSAS CORPORATION COMMISSION  
JUL 29 2016  
CONSERVATION DIVISION  
WICHITA, KS