

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26834-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 12-12S-19W
915 feet from S Section Line, 1030 feet from E Section Line
Lease Name: RATTLESNAKE Well #: 1
County: ELLIS Total Vertical Depth: 3810 feet

Operator License No.: 4787
Op Name: TDL, INC.
Address: 1310 BISON RD
HAYS, KS 67601

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
SURF	8.625	221		250 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/29/2016 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY Company: SOUTHWIND DRILLING, INC. Phone: (620) 564-3800

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE WitnessType: NONE
Date/Time Plugging Completed: 06/29/2016 9:30 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

1st plug @3778 w/50 sx
2nd plug @1550 w/50 sx
3rd plug @830 w/100 sx
4th plug @270 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

JUL 01 2016

Received
KANSAS CORPORATION COMMISSION

JUL 08 2016

CONSERVATION DIVISION
WICHITA, KS

JUL 29 2016

Form CP-2/3