

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-079-20374-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 15-22S-2W  
4656 feet from S Section Line, 4933 feet from E Section Line  
Lease Name: GRABER B Well #: 1  
County: HARVEY Total Vertical Depth: 4328 feet

Operator License No.: 5399  
Op Name: TREK AEC, LLC  
Address: 200 W DOUGLAS, SUITE 101  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3825		200 SX
SURF	8.625	209		200 SX

Well Type: SWD UIC Docket No: D21326.0 Date/Time to Plug: 05/19/2016 12:00 AM

Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: DAVID BRADY Company: Phone: (620) 727-3410

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK  
Date/Time Plugging Completed: 06/10/2016 4:00 PM

WitnessType: PARTIAL  
KCC Agent: B. J. HOPE

Actual Plugging Report:

5/19/16 PULLED 129 JTS FIBERGLASS TUBING. 5/20/16 - SET BRIDGE PLUG AT 3792', SETTING TOOL HUNG UP IN CASING, COULD NOT GET FREE, PULLED SLIPS, HAD ONLY 4" STRETCH, PERFORATED AT 420', PUMPED 170 SX CEMENT TO SURFACE. 5/23/16 CHECKED TOP PLUG, CUT HEAD OFF, FELL BACK 180' INSIDE AND 91' OUTSIDE. 6/9/16 ONE INCHED INSIDE 5.5" WITH 75 SX OF CEMENT, ONE INCHED BETWEEN 8 5/8" & 5.5" WITH 25 SX. 6/10/16 CHECKED TOP PLUG STAYED AT SURFACE.

Perfs:

Remarks: QUALITY WELL SERVICE PROVIDED ALL THE CEMENT FOR THIS JOB. WELL PLUGGED BECAUSE OF FAILED MIT.

Plugged through: TBG

*MD*  
*JL 29 2016*  
*CC UIC*

District: 02

Signed *B. J. Hope*

(TECHNICIAN)

KCC WICHITA

JUL 19 2016 Form CP-2/3

RECEIVED

*JK*