

KANSAS

FORM CP-3
Rev, 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-009 21,252-0000

245 North Water
Wichita, KS 67202

Operator's Full Name Hummon Corporation

Complete Address 400-One Main Place, Wichita, Kansas 67202

Lease Name Foster Well No. 1

Location W $\frac{1}{2}$ NE NE Sec. 5 Twp. 16S Rge. 11 ~~Base~~ (West)

County Barton Total Depth 3280'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Clarke Corp. & Allied Cementing Co.

Address 107 W. Fowler, Medicine Lodge Ks. License No.

Operation Completed: Hour 11:15 Day 17 Month 4 Year 1981
AM

The above well was plugged as follows:

Sanded back to 2925' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 400# hulls,

17 sx mud-gel, 100# hulls, 25 sx cement, 3 sx mud-gel,

plug, and 100 sx cement.

Max. pres. 1000#. Shut in pres. 900#.

Recovered 2074' of 5 1/2" casing.

Top perforation at 2974'.

3275' of 5 1/2" casing cemented with 100 sx cement.

275' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane L Rankins
Conservation Division Agent

DATE 5-15-81

INV. NO. 5348-w

RECEIVED
APR 21 1981
4-21-81
CONSERVATION DIVISION
Wichita, Kansas