

15-195-01375-0001 <sup>0000</sup>

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 14-4

LOCATION SE SE NE

SEC. 28 TWP. 12 RGE. 22 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. B-1 / Lease Anderson B-1

Operator Stanolind Oil & Gas Address Box 488 Hays, Kans

Field \_\_\_\_\_ County Trego

Total Depth 4103 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 3/8" at 198' circulated with cement - 5 1/2" at 4096' with 300 sax cement behind.

Sand to 4080', set 4 sax cement with dump bailer, pulled 1080'

5 1/2" - filled with mud to 198', set rock and 15 sax cement, mud

to 35', set rock and x 10 sax cement to bottom cellar.

Edw. Kelly  
District Conservation Agent

Date 10-21-55

**PLUGGING**  
FILE SEC 28 TWP. 12 RGE. 22 W  
BOOK PAGE 14 LINE 4

RECEIVED  
OCT 26 1955  
10-26-55  
CONSERVATION DIV.  
Wichita, Kansas