

15-009-071840000

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 12-43

LOCATION SW-SW-SW

SEC. 6 TWP. 16 RGE. 11W

Dry Hole Abandoned Oil Well Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Woydzisk

Operator Calder Oil & Ref. Co. Address 301 S. Mkt. Wichita, Kans.

Field County Barton

Total Depth 3332 Feet.

Plugging Contractor R & S. Pipe Pulling Co.

Plugging Contractor's License No. 1.

Address Ellinwood Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 1/2" @ 522' C.W.C. Oil string 5 1/2" O.D.
w/ 75 sk Cem. @ 3324 Cement inside pipe drilled
out to 3067' Top perf. 3046' Filled back with
sand to 3030' and dumped 5 sk Cem. Shot off
and pulled 5 1/2" casing. Filled hole with mud
to 275' set rock bridge and run 20 sk of Cem.
mud to 25' rock bridge and 10 sk of Cem
to base of cellar.

PLUGGING
FILE SEC 6 TWP 16 RGE 11W
BOOK PAGE 12 LINE 43

3-8-54

Warren H. Horner
District Conservation Agent
Date Mar. 5, 1954